


15-077-10066-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Harper County. Sec. 7 Twp. 31 Rge. 8 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW NE SE  
Lease Owner Beardmore Drilling Co.  
Lease Name Wingate #1 Well No.  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 6-8-59 19  
Plugging completed 6-13-59 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hample  
Producing formation Depth to top Bottom Total Depth of Well 4438 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	217'	none
				5-1/2"	4419'	3561'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 4438' and found it open.  
Filled w/sand to 4400' and ran 5 sacks of  
cement with bailer. Pulled 5 1/2" casing,  
cleared hole and bailed to 200', set 10'  
rock bridge and dumped 20 sacks of cement.  
Mudded the hole to 40', set 10' rock bridge  
and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1959  
7-15-59  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co.  
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.  
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CVhase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of June, 19 59

My commission expires 9-27-62

Thomas V. Dyke Notary Public.

PLUGGING  
FILE SEC. 7 T. 31 R. 3W  
BOOK PAGE 41 LINE 37

BEARDMORE  
 #1 Wingate  
 SW NE SE Section 7-31S-8W  
 Harper County, Kansas

Drilled by: Beardmore Drilling Company  
 Drilling Commenced: 9-20-57  
 Drilling Completed: 10-2-57

Casing Record: Ran 219' of 8-5/8" set at 217' with 135 sacks, cement circulated.  
 9-20-57.  
 Set 5-1/2" at 4419' with 60 sacks cement. 10-2-57.

Elevation: 1659 KB  
 1656 DF  
 1654 GR

<u>FORMATIONS</u>	<u>DEPTH</u>
Surface Soil	20
Sand	100
Red Bed and Shale	217
Shale	1400
Shale and Lime	1600
Shale and Lime	2200
Shale and Lime	3160
Shale and Lime	3500
Shale	3575
Shale and Lime	3592
Lime	3810
Shale and Lime	3895
Shale and Lime	3950
Lime	4015
Shale and Lime	4075
Lime	4175
Shale and Lime	4230
Chert and Lime	4417
Chert	4432
Lime	4435
Rotary Total Depth	4435
Cable Tool Total Depth	4438

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 15 1959  
 7-15-59  
 CONSERVATION DIVISION  
 Wichita, Kansas

<u>TOPS</u>	
Mississippi	4406

DST #1 4407-4417 Shut in 15 min., open 1 hr., gas in 5 min., at end of 1 hr. testing 190,000 cfg, shut in 15 min. Recovered 80' gas cut mud, few specks oil. IBHP 1612, FBHP 1450, IF 41, FF 55.

DST #2 4418-4432 Shut in 15 min., open 1 hr., good blow, shut in 15 min. Recovered 140' slightly oil and gas cut mud. IBHP 1578, FBHP 622, IF 42, FF 68.

STATE OF KANSAS            )  
   ) ss:  
 COUNTY OF SEDGWICK    )

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

BEARDMORE DRILLING COMPANY  
 PLUGGING  
 FILE SEC 7 T31 R3W By  
 BOOK PAGE 41 LINE 37  
*Al Beardman*

Subscribed and sworn to before me this 21st day of November, 1957.

My commission expires: 4-9-60. *Barbara Springsteen*  
 Barbara Springsteen - Notary Public