

15-077-19011-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None

LEASE NAME Grabs

WELL NUMBER B-2

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 7 TWP. 31S RGE. 8 (R) or (W)

COUNTY Harper

Date Well Completed 5/25/64

Plugging Commenced 2/8/91

Plugging Completed 2/13/91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

Amended

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE#(918 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by n/a (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, is well log attached? -

Producing Formation Miss. Depth to Top 4430 Bottom 4440 T.D. 4500

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Miss.	Oil	4430	40	8 5/8	216	None
				4 1/2	4499	3248

APR 20 1991
4-29-91
KANSAS CORPORATION COMMISSION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 4380' & dumped 4 sxs cmt. Shot pipe @ 3248'. POOH & LD. Spotted 35 sxs cmt @ 1200', 35 sxs @ 900', and 100 sxs @ 300' and circulated to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P. O. Box 347, Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kaiser-Francis Oil Company

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 26th day of April, 19 91

Judith E. Jewell
Notary Public

My Commission Expires: 3-29-92

15-077-19011-0000

SAFARI-UNIT, INC.
WICHITA, KANSAS
DRILLER'S WELL LOG

WELL NO.
SECTION 7-316-37
HARPER COUNTY, KANSAS

COMMENCED: MAY 13, 1964
COMPLETED: MAY 25, 1964

OPERATOR - MOORE OIL COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	115	SAND	
115	151	RED BED	
151	500	RED BED & SHALE	RAN 7 JOINTS 2-5/8" CASING, SET @ 216' W/ 175 BAGS CEMENT
500	1000	SHALE	
1000	1500	SHALE & LIMESTONE	
1500	1955	LIME	
1955	3195	LIME & SHALE	
3195	3410	LIME	
3410	3725	LIME & SHALE	
3725	4425	LIME	
4425	4900	CHERTY LIME	
4900	TO		RAN 4499' OF 4-1/2" CASING, SET @ 4499' W/ 100 BAGS CEMENT

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN SECTION 7-316-37, HARPER COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE ON THIS 1st DAY OF JUNE, 1964 PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES OCTOBER 2, 1967

Vera A. McKenzie
VERA A. MCKENZIE, NOTARY PUBLIC

12-5-90
CONSERVATION DIVISION
WICHITA, KANSAS