

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Harper County. Sec. 7 Twp. 31S Rge. (E) 8 (W)  
Location as "NE1/4NW1/4SW1/4" or footage from lines C, SW/4, SW/4, SW/4,  
Lease Owner R. C. Patton Co., & Drillers Gas Co.,  
Lease Name R. M. Wingate Well No. 1  
Office Address 612 Orpheum Bldg. Wichita 2, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 30 19 48  
Application for plugging filed October 20th 19 48  
Application for plugging approved October 21 19 48  
Plugging commenced October 21th 19 48  
Plugging completed October 30 19 48  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Turkee  
Producing formation Depth to top Bottom Total Depth of Well 4930 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Mids. Lime	Show Oil & Gas	4385	4512	10" 5 1/2"	353 4812	None 3315'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set Lane - Wells plug at 4560ft. Set Lane - Wells Plug at 4459 FT.  
Plugged back to 4431ft. With Cement and Lead wool. Set Retainer at 4391ft.  
Squeezed Oil & Water from 400ft. to 4413ft. with 200 Sacks Cement, Mud to 4316ft. Bridged at 4316ft. Dumped 5 Sacks Cement 4316ft. Shot Pipe at 3300ft.  
Pulled Pipe, and mudded hole to 200 ft. Dumped 15 Sacks of Cement at 200 ft.  
Finished mudding hole and put 4 Sacke of Cement at top of Surface.

RECEIVED  
Conservation Div.  
11-5-48  
NOV 5 1948  
STATE CORPORATION  
COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to R. C. Patton Co.,  
Address 612 Orpheum Bldg Wichita 2, Kansas.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
R. C. Patton (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R.C. Patton  
612 Orpheum Bldg. Wichita 2, Kansas.  
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of November 19 48

R. P. Hendrick  
Notary Public.

My commission expires Oct 4th 1952.

PLUGGING  
FILE SEC 7-T 31 R 80  
BOOK PAGE 63 LINE 36

R. C. Patton Co., Drillers Gas Co.,  
R. M. Wingate Well #1

Center SW $\frac{1}{4}$ , SW $\frac{1}{4}$ , SW $\frac{1}{4}$ , Sec 7, T31S,  
R8W, Harper County, Kansas.

CASING RECORD  
10" Casing at 253Ft.  
200 Sacks of Cement  
5 $\frac{1}{2}$ " Casing at 4812Ft.  
200 Sacks Cement.

Total Depth 4930Ft.  
Comm. 7/21/48  
Comp. 10/30/48  
Contractor R. C. Patton Co.,,

Sand & Gravel	97
Red Rock	180
Water Gravel	200
Red Shale	488
Shale	760
Shale & Shells	1245
Salt	1340
Shale & Shells	1440
Lime	1565
Lime & Shale	1735
Lime	1835
Lime & Shale	2040
Lime	2075
Lime & Shale	2950
Shale	2996
Lime	3040
Shale	3083
Lime	3260
Lime & Shale	3496
Shale Sandy	3550
Lime	3577
Shale	3609
Sand & Shale	3633
Lime Sandy	3662
Lime	3896
Lime & Shale	3915
Shale	3952
Lime Brown	3972
Lime Soft	3993
Lime	4112
Lime & Shale	4176
Shale	4252
Lime & Shale	4285
Lime &	4308
Lime & Shale	4332
Shale	4385
Lime Cherty	4400
Chat	4403
Chirt Soft	4455
Chat & Shale	4511
Shale	4548
Lime & Shale	4590
Lime	4606
Lime & Shale	4670
Shale	4730
Lime Cherty	4776
Lime & Sand	4817
Lime Cherty	4829
Sand	4839
Chert	4841
Shale	4907
Lime	4930
Total Depth	4930

TOPS

Fort Riley	1710
Douglas	3410
Kansas City Lime	3635
Marmaton	4130
Miss. Lime	4385
Kinderhook	4556
Viola	4726
Simpson	4770
Siliceous Lime	4907

RECEIVED

Conservation Div.

11-5-48  
NOV 5 1948

STATE CORPORATION  
COMMISSION  
KANSAS

STATE OF Kansas COUNTY OF Sedgwick SS,

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

PLUGGING

FILE SEC 7 T 31 R 8w  
BOOK PAGE 63 LINE 36

Subscribed and sworn to before me this 4th day of November 1948

R. C. PATTON CO.,

By R. C. Patton

J. P. Kendrick  
Notary Public.

My Commission expires Oct 4th 1952