

15-017-00846-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

TYPE OR PRINT
NOTICE: Fill out Completely
and return to coms. div.
office within 30 days.

SWD
API NUMBER _____
LEASE NAME CE Warren
WELL NUMBER SWD 1
4290 ft. from S Section Line
4950 ft. from E Section Line
SEC. 17 TWP. 31 RGE. 8 (E) or (W)
COUNTY Harper
Date Well Completed _____
Plugging Commenced 11/29/01
Plugging Completed 11/30/01

LEASE OPERATOR McCoy Petroleum Corporation
ADDEESS 453 S. Webb Rd., Suite 310, Box 780208, Wichita, KS
PHONE # (620) 636-2737 OPERATORS LICENSE NO. 5003
Character of well SWD

(Oil, Gas, D&A, SWD, input, Water Supply Well)

The plugging proposal was approved on 11/29/01 (date)
by Doug Louis (XCC District Agent's Name).

Is ACO-1 filed? yes if not, Is well log attached? not available to us

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4423

Show depth and thickness of all water, oil and gas formations

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	227	none
				5 1/2	4423	1422

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set

Sand at 3881, baled 5 sacks cem. Bridge plug at 2750, baled 5 sacks cem. Shot pipe at 1422, pulled to 1300, pumped 35 sacks cem. Pulled to 700, pumped 35 sacks cem. Pulled to 310, circulated cem. to surface w/75 sacks. Laid down rest of pipe.

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925
Address 401 West Main, Lyons, KS 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Scott Hampel (Employee of Operator) or (Operator) of
above - described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above - described well as filled that
the same are true and correct, so help me God.

(Signature) Scott Hampel
(Address) PO Box 780208 Wichita, KS 67278-0208

10th day of December, 2001

Dianne Howard

Notary Public



Form CP-4
Revised 05-88

RECEIVED
DEC 12 2001
KCC WICHITA

My commission Expires: 3/15/03