

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

Form CP-4  
Rev. 12-15-80

AUG 02 1982

CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barber SEC. 14 TWP. 33 RGE. 12W E/W  
Location as in quarters or footage from lines:  
C NE NE


Locate Well  
correctly on above  
Section Platt.

Lease Owner Okmar Oil Company  
Lease Name Groendyke #1 Well No. \_\_\_\_\_  
Office Address Box 723 Hays, Kansas 67601  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 5-22-82  
Plugging completed 7-26-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	250'	none
				5-1/2"	3917'	2804'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped bottom plug to 3397' with 50 sacks cement. Shot casing @3001', 2906' and 2820'. Pulled a total of 87 joints of 5-1/2" casing. Plugged well with 5 sacks hulls, 25 sacks gel, 8-5/8" plug, 150 sacks 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 82

My Commission expires:



Irene Hoover  
Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: Okmar Oil Company DRILLING COMMENCED: November 3, 1971  
 1130 Vickers-KSB&T Bldg.  
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: November 14, 1971  
 505 Union Center  
 Wichita, Kansas 67202

CASING RECORD: 6 Jts. 250' 8-5/8" cemented with 225 sacks.  
 122 Jts. 3917' - 5-1/2" cemented with 150 sacks

LOCATION: Groendycke No. 1  
 C NE NE  
 Section 14-33S-12W  
 Barber County, Kansas

-----

0 - 620	Red bed & shale
620 - 1325	Shale & shells
1325 - 1740	Shale with lime streaks
1740 - 3461	Lime & shale
3461 - 3560	Sand, shale & lime
3560 - 3645	Shale & sand
3645 - 3722	Lime & shale
3722 - 3750	Sand & shale
3750 - 4330	Lime
4330 - 4387	Lime & shale
4387 - 4496	Lime
4496	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *John H. ...*  
President

STATE OF KANSAS )  
                          ) ss.  
BUTLER COUNTY )

Subscribed and sworn to before me, a Notary Public, this 19th day of November, 1971.

*Betty Brandt*  
Betty Brandt Notary Public

My commission expires:

May 9, 1975

*Copy to Corporation Commission  
Copy to Well Log Bureau*

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1982  
CONSERVATION DIVISION  
Wichita, Kansas