


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

BARBER County. Sec. 18 Twp. 31 Rge. 15W(E)____(W)
Location as "NE/CNW*SW*" or footage from lines NE SW SW
Lease Owner SANTA FE PIPE & SUPPLY
Lease Name ROBBINS-GALLUP Well No. 1
Office Address P. O. BOX 562 - GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed OCTOBER 6 19 61
Application for plugging filed JULY 31 19 62
Application for plugging approved AUGUST 1 19 62
Plugging commenced AUGUST 16 19 62
Plugging completed AUGUST 23 19 62
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well HERMAN JUSTUS
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4806' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	285'	NONE
				4 1/2"	4801'	4389'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4445' - 4400' - FILLED WITH SAND
 4400' - 4360' - 5 SACKS CEMENT
 4360' - 285' - MUD
 285' - 275' - ROCK BRIDGE
 275' - 215' - 20 SACKS CEMENT
 215' - 40' - MUD
 40' - BASE - 10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GLENN & SMITH PIPE PULLING COMPANY
Address P. O. BOX 114 - ELLINWOOD, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt
P. O. BOX 562 - GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 6 day of OCTOBER, 1962

My commission expires JULY 31, 1966
Mary M. Guesnier Notary Public.



b

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. KENNETH RUPP & BOA
Farm. Robbins-Gallup Unit No. 1

SEC. 18 T. 31 R. 15W
Approx. C SW

Total Depth. 4806'
Comm. 9-21-61 Comp. 10-6-61
Shot or Treated.
Contractor. Red Tiger Drlg. Co.
issued. 3-31-62

County Barber
KANSAS



Elevation. 1913' DE

Production. 65 BOPD

CASING:

8 5/8" 285' cem w/175 sx.
4 1/2" 4801' cem w/100 sx.

Figures Indicate Bottom of Formations.

rock & soil	75
gyp & rock	145
shale & shells	375
red bed & shells	1000
shale & shells	1545
salt & shale	1680
shale & shells	2037
lime & shale	2460
sandy lime & shale	2555
lime & shale	3673
lime	3715
lime & shale	3815
sandy lime & shale	3853
lime & shale	4245
lime	4615
lime & shale	4710
Mississippi	4806
Total Depth	

TOPS: SCOUT

Lansing	4144
Marmaton	4628
Cherokee	4684
Ero. Mississippi	4703
Mississippi	4736

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 1962
CONSERVATION DIVISION
Wichita, Kansas