

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,470-00-00

LEASE NAME LENKNER

WELL NUMBER C-1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 4 TWP. 31 S RGE. 15 ~~00~~ (W)

COUNTY BARBER

LEASE OPERATOR GOULD OIL, INC.

ADDRESS 110 NORTH MARKET WICHITA, KS. 67202

PHONE#(316) 265-5523 OPERATORS LICENSE NO. 5298

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed

Plugging Commenced 12-4-91

Plugging Completed 12-11-91

The plugging proposal was approved on DEC. 10, 1991 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is ACO-1 filed? YES If not, Is well log attached?

Producing Formation EMPORTA Depth to Top Bottom T.D. 4570

PBTD: 4250

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	265	8 5/8	265	0
		0	4568	4 1/2	4568	1893FT 45 JTS.

DEC 23 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

SET PLUG AT 3000 FT, PUMPED 2 SX OF CEMENT ON TOP OF PLUG. CUT AND PULLED CASING AT 1893 FT, 45 JTS.

TOP HOLE PLUG: 3 SX HULLS, 10 SX GEL, 50 SX CEMENT, 10 SX GEL, 100# HULLS, 8 5/8 PLUG

100 SX CEMENT, 40-60 POZ, 6% GEL, MAX PRESSURE: 500 # ISIP: 200#

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P O BOX 847 PRATT, KS.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GOULD OIL, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

PLUGGING CONTRACTOR
(Employee of ~~XXXXXXXXXXXXXXXXXXXX~~)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PWS, Inc.



TESTED AND SWORN TO before me this 20th day of Dec., 19 91

Dorothy M. Ferguson
Notary Public

My Commission Expires: Feb. 6, 1993