

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barber County, Sec. 4 Twp. 31S Rge. 15 EXW

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_

185' N of C NE NW

Lease Owner Gould Oil, Inc.

Lease Name Lenkner Well No. 2

Office Address P. O. Box 8640, Wichita, Kansas 67208

Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Dry Hole

Date Well completed 06-06 1981

Application for plugging filed 06-06 1981

Application for plugging approved 06-06 1981

Plugging commenced 06-06 1981

Plugging completed 06-06 1981

Reason for abandonment of well or producing formation \_\_\_\_\_

Dry Hole

If a producing well is abandoned, date of last production 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes \_\_\_\_\_

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4787'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE  | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
|           |         |      |    | 8 5/8 | 285    |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |
|           |         |      |    |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

plugged at 7:45 A.M. 06-06-81 with common cement 3 cc, 2 % gel, 40 sacks @ 285' 10 sacks @ 40' 10 sacks @ rathole, 5 sacks @ mouse hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Eagle Drilling

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Bob Eisel (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert J Eisel

(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 16th day of June, 1981


Carolyn M Sloderbeck  
Notary Public.

RECEIVED

STATE CORPORATION COMMISSION

JUN 19 1981

CONSERVATION DIVISION  
Wichita, Kansas



DRILLER'S LOG

Operator: Gould Oil, Inc.  
Lease Name: Lenkner #2  
Spot Location: 185' N or C NE, NW  
Sec. 4-31 S - 15W  
County, State: Barber County, Kansas

Commenced: 05-27-81  
Completed: 06-06-81

Surface Casing: Ran 6 joints of new 24lb.,  
8 5/8" casing. Cemented w/275 sacks of common  
3% cc, 2% gel. Cement did circulate.

FORMATION

DEPTH

|                     |             |
|---------------------|-------------|
| Red Rock and Gypsum | 0 - 70      |
| Sand and Red Bed    | 70 - 285    |
| Red Bed             | 285 - 570   |
| Shale               | 570 - 1350  |
| Shale and Shells    | 1350 - 1855 |
| Shale               | 1855 - 2140 |
| Shale and Lime      | 2140 - 4212 |
| Lime                | 4212 - 4800 |
| RTD                 | 4800        |

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

EAGLE DRILLING, INC.

*John Miles*  
John Miles  
Controller

RECEIVED  
STATE CORPORATION COMMISSION

JUN 19 1981

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) ss:

Subscribed and sworn to before me this 17th day of June, 1981.

My appointment expires

**CAROLYN G. SLODERBECK**  
**NOTARY PUBLIC**  
**STATE OF KANSAS**  
MY APPT. EXPIRES 12 May 1985

*Carolyn G. Sloderbeck*  
Notary Public