

State of Kansas



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN P. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 14 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. M. F. Moeller of Curt Brown Drilling Co. has this date requested permission to plug the following described well:

Mr. Moeller guarantees payment of the plugging fee.

Operator's full Name: Appleton Oil Company

Complete Address: 506 Beacon Bldg., Tulsa, Oklahoma

Lease Name: Schupbach Well No. # 1

Location: NE SE NE Sec. 10 Twp. 34 Rge. 11 (E) (W) W

County Barber Total Depth 4650' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Moeller was instructed to plug the well as follows:

345' of 8 5/8" surface pipe, cement circulated with 325 sacks.
Fill hole with drilling mud to 300', 1st cementing plug, bridged
with hulls, and cemented with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base of the cellar. Bridge and cement rat hole
with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent