

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1966
7-19-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Pepe Musgrove of Hellar Drilling Co., Inc has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Roy D. McAninch

Complete Address: 1363 First National Bldg., Oklahoma City, Okla.

Lease Name: Dorothy Well No. # 1

Location: C SW NE Sec 26 Twp. 34 Rge. 11 (E)(W) W

County Barber Total Depth 4690' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

301' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill hole with drilling mud to 275', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent