

15-007-30282-00-00

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

FILED IN THE
STATE CORPORATION COMMISSION

DEC 19 1966
12-19-66

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Nelson of Walters Drilling Company has this date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Ferguson Oil Company

Complete Address: 1505 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Walker Well No. # 1

Location: C SW NE Sec. 28 Twp. 30 Rge. 15 (E)(W) W

County Barber Total Depth 4443' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nelson was instructed to plug the well as follows:

63' of 13 3/8" surface pipe, cemented with 80 sacks. 797' of 8 5/8" surface pipe, cement circulated with 500 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent