

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

AUG 29 1908

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Co. has this

date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Kimbark Exploration Co.

Complete Address: 201 University Blvd., Denver, Colorado

Lease Name: Riepe Well No. # 1

Location: SE SW Sec. 28 Twp. 30 Rge. 15 (E) (W) W

County Barber Total Depth 4693 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

1020' of 8.5/8" surface pipe, cement circulated. Fill
hole with mud to 1000', 1st cementing plug, 1/2 sack hulls,
cement with 30 sacks. Fill hole with mud to 40', 2nd
cementing plug, 1/2 sack hulls, cement with 15 sacks to
base cellar. Cement rat hole with 2 sacks.

These plugging orders were given by Hugh Scott, Sublett, Ks.
 Very truly yours,

Archie Elving
 Conservation Division Agent