

State of Kansas



15-007-30315-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 5 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Nelson of Walters Drilling Company has this date requested permission to plug the following described well:

Mr. Nelson guarantees payment of the plugging fee.

Operator's full Name: Birmingham-Bartlett Drilling Company

Complete Address: 300 Kaufman Bldg., Wichita, Kansas

Lease Name: Mills Well No. # 1

Location: ~~C SW SE~~ C SE SW Sec. 34 Twp. 30 Rge. 15 (E)(W) W

County Barber Total Depth 4572' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Nelson was instructed to plug the well as follows:

791' of 8 5/8" surface pipe, cement circulated with 425 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack hulls, and cement with 25 sacks of cement. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to the base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent