

DISTRICT CONSERVATION AGENT'S REPORT

Handwritten initials/signature

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE-SE-SE

SEC. 29 TWP. 30 RGE. 13W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Sadie Clay

Operator J. M. Huber - Corp. Address Box #460 Pratt-Kansas-

Field _____ County Boebee

Total Depth 4620 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 800ft - Circulated with cement
5 1/2 casing set at 4613ft - Plugged back to 4300ft
with sand & chat - Pumped 5 sacks of cement at 4300ft -
Shot off & Pulled the 5 1/2 casing - Filled with mud
to 250ft - Set Rock Bridge & 20 sacks of cement at 250ft
Mud to 30ft - Plug & 10 sacks of cement
at the surface

MAY 16 1950 5-16-50

R. M. Stough
District Conservation Agent

Date 5-13-50

PLUGGING
FILE SEC 29 T 30 R 13W
BOOK PAGE 5 LINE 36