

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1966
1-3-66
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Shenandoah Oil Corporation

Complete Address: 406 Mutual Savings Bldg., Fort Worth, Texas

Lease Name Birdie B. Clarke Well No. # 1

Location C S/2 S/2 SW Sec. 7 Twp. 34 Rge. 13 (E) (W)

County Barber Total Depth 4900'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 2:00PM Day 30th Month Dec. Year 1966

The Above well was plugged as follows:

381' of 8 5/8" surface pipe, cement circulated with 250 sacks. Hole
was filled with drilling mud to 350', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 350', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 1/4/67
INV. NO. 4555-W