

DISTRICT CONSERVATION AGENT'S REPORT

R *CPB*

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. NE 9ENW

LOCATION ~~Sec 22~~

SEC. 22 TWP. 30 RGE. 13W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Gaut

Operator J. M. Heber, Corp. Address Box #460 Peatt, Kans.

Field _____ County Barber

Total Depth 4593 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 895 ft. Circulated with cement.
5 1/2" casing set at 4574 ft. Plugged back from
bottom to 4570 ft with sand & shot. Dumped
5 sacks of cement at 4570 ft - Shot off & pulled
the 5 1/2" casing - Filled with mud to 950 ft. Set
Block Bridge & 20 sacks of cement at 950 ft
Mud to 30 ft - Bridge & 10 sacks of cement
at the surface

MAY 31 1950 5-31-50

C. D. Slough
District Conservation Agent

Date 5-27-50

PLUGGING
FILE SEC 32 T 30 R 13W
BOOK PAGE 8 LINE 34