

To: 1041168  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

15-007-00526-00-01  
API NUMBER 15-Drill completion date 7/3/54

SE NW SW, SEC. 6, T 34 S, R 13 W/E  
1650 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT 4-22  
Operator License # 5447

Lease Name Ott B Well # 1

Operator: OXY USA Inc.  
Name & Address: 110 S. Main, Ste. 800  
Wichita, KS 67202

County Barber 162.82  
Well Total Depth 5010 feet

Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 354

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:30 a.m. Day: 22 Month: 4 Year: 19 96

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

was: 5 1/2" at 5010' w/125 sx cement, PBD 4977', Perfs at 4868-95'

1st plug sand back to 4800' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 22 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4790' and dumped 5 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 150 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3300' of 5 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED (if requested) observe this plugging.

DATE APR 29 1996

INV. NO. 45470

Signed Steve Pfeifer (TECHNICIAN)

RECEIVED  
KANSAS CORP COMM  
10:59  
APR 29