

To: 1 041299
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 207B
Wichita, KS 67202

4-2

API NUMBER 13-007-01461-00-01

TECHNICIAN'S PLUGGING REPORT

C N/2 N/2 W/4 SEC. 7, T 34 S, R 13 W/4

RECEIVED _____ feet from S section line

ANSAS CORP COMI 4-9-98 _____ feet from E section line

1998 APR -9 12:26

Operator License 16006

Lease Name Blunk Well # 3

Operator: Molz Oil Company

County Barber 173.39

Name: RR# 2, Box 54

Well Total Depth 5335 feet

Address: Kiowa, KS. 67070-0054

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 434'

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS.

Company to plug at: Hour: 9:45 AM Day: 2 Month: 4 Year: 1998

Plugging proposal received from Non Vital

(company name) Clarke Corporation (phone) 316-886-5665

work: 4 1/2" @ 5021' w/ 150 sx. cement, PBT D @ 5021, Perfs @ 4944-4952

1st plug set cast Iron Bridge Plug @ 4890' & dump 2 sx. cement on top of ^{C.I.B.P.} ~~surface~~ bailer,

2nd plug pump down 8 5/8" surface pipe w/ 300# hulls, 10 sx gel, 50 sx. cement, 10 sx. gel,

100# hulls, 8 5/8" wiper plug & 100 sx. cmt.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 AM Day: 2 Month: 4 Year: 1998

ACTUAL PLUGGING REPORT 1st plug set c.i.b.p. @ 4890' & dumped 2 sx cmt. on top of

C.I.B.P. through bailer,

2nd plug pumped down 8 5/8" surface pipe w/ 300# hulls, 10 sx gel, 50 sx. cmt, 10 sx gel,

100# hulls, 8 5/8" wiper plug & 100 sx. cmt.

max. psi = 200# S.I.P. = 100#

Remarks: used 4000oz mix 6" gel by Allied. Recovered 3100' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 15, 1998 serve this plugging.

INV. NO. 50351

Signed Stephen J. Puffer
(TECHNICIAN)