

To: 1 041159
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 007-22,385-00-00 207
N/2 NE NW, SEC. 9, T. 34 S, R. 13 W/E
530 feet from N & section line
3310 feet from E section line

3-28
TECHNICIAN'S PLUGGING REPORT

Operator License / 30604
Operator: Raydon Exploration, Inc.
Name & Address: P.O. Box 1816
Liberal, KS 67905-1816

Lease Name Donovan Well # 1-9
County Barber 164.93
Well Total Depth 5075 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 433

Abandoned Oil Well _____ Gas Well Input Well _____ SMD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Jerry Duncan, Inc. License Number 8733
Address P.O. Box 389, Enid, OK 73702

Company to plug at: Hour: 10:15 a.m. Day: 28 Month: 3 Year: 19 96

Plugging proposal received from Ray Bennett
(company name) Jerry Duncan, Inc. (phone) 405-237-6152

were: 4 1/2" at 5075' w/150 sx cement, PBTD 5051', Perfs at 4866-72, 4873-89, 4935-50'
1st plug pump 20 bbls. drilling mud and 25 sx cement,
2nd plug spot 40 sx cement at 1500' through 4 1/2" casing,
3rd plug spot 70 sx cement at 500',
4th plug spot 10 sx cement at 40'.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 28 Month: 3 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 20 bbls. of drilling mud and 25 sx cement. Stopped plug at 4578'. Displaced hole with drilling mud & spotted plugs through 4 1/2" casing:

2nd plug at 1500' with 40 sx cement,
3rd plug at 500' with 70 sx cement,
4th plug at 40' with 10 sx cement.

Remarks: Used Class H cement by Jerry Duncan, Inc. Recovered 2500' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and/or my agents) observe this plugging.

DATE APR 11 1996
INV. NO. 45187

Signed Stephen J. Pfeifer (TECHNICIAN)

STATE CORPORATION COMMISSION RECEIVED
APR 4 1996 4-4-96
WICHITA, KANSAS