

1 040428

API NUMBER 15- 007-22,312-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E/2 W/2 NE NE, SEC. 9, T 34 S, R 13 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Operator: American Energies Corporation
Name & Address: 155 N. Market, Suite 710
Wichita, KS 67202

4620 feet from S section line

820 feet from E section line

Lease Name Donovan Well # G#1

County Barber 164.45

Well Total Depth 5060 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 8 a.m. Day: 10 Month: 6 Year: 1990

Plugging proposal received from Vince Schrappe

(company name) Allen Drilling Company (phone) 316-793-7423

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1824'
Anhydrite 824-50'

1st plug at 850' with 50 sx cement,

2nd plug at 420' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:30 a.m. Day: 10 Month: 6 Year: 1990

ACTUAL PLUGGING REPORT 1st plug at 847' with 50 sx cement,

2nd plug at 412' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services.

(If additional description is necessary, use BACK of this form.)

INVOICED observe the plugging.

DATE 6-27-90

INV. NO. 28498

CONSERVATION DIVISION
Wichita Kansas

Signed Stephen J. Pfeifer
(TECHNICIAN)