

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-121-20079-00-00

Spot: SWSWSW Sec 22 Twp 16 S Rng 23 E / W
85 Feet from N / S Line of Section
4646 Feet from E / W Line of Section

GPS: Lat: 38.636210 Long: 94.861750 Date: 8/15/13

Lease Name: Peak (27098 Hospital Dr. Paola) Well #: PEA 01

County: Miami Total Vertical Depth: 430 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>SURF - Casing</u>	<u>7.000</u>	<u>20</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>130 S. MARKET</u>	<u>T1 - Tubing 1</u>	<u>2.000</u>	<u>420</u>	<u>0</u>	<u>EST.</u>
Address 2: _____	<u>PKR - Packer</u>	<u>0.750</u>	<u>410</u>	<u>410</u>	
City: <u>WICHITA</u>					
State: <u>KS</u> Zip Code: <u>67202</u> - _____					

Well Type: RES - Residential Gas Well - (GAS) UIC Docket No.: _____ Date/Time to Plug: 8/20/13 / _____
 Plug Co License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC.
 Proposal Rcvd from: Mike Kepley Company Name: KWS Phone: (620) 431-8945

Proposed
 Plugging
 Report:

Run pipe to TD. Pump Portland cement from TD to surface. Perforate well if not documented Alt.II.

Plugging Proposal Received By: Frank Guilfoyle Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 8/20/13 / _____ KCC Agent: Frank Guilfoyle

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
Move equipment to location. Work 3/4" inch pipe and packer loose. Pull out 150 ft and hit tight spot. Pull packer off. Pull rest of pipe out. Run in 2" bit and worked to 200 ft. Pull bit out. Run in spring loaded overshot. Didn't grab anything. Pull out. 2" fell, wash 1" to 430 ft inside and hit solid. Wash 3/4" inside 2"PVC to 430 ft and hit solid. Pump Portland cement from TD to surface inside surface and inside 2" PVC. Pull 1" and 3/4". Top off well. Pump total of 112 sacks of Portland cement. Well plugged.				

Remarks: Contract # 11782. Control # 20140019-001. Category 1. GPS by TH, FG. Reg. Sect. NAD83

Plugged Thru: TBG - Tubing **RECEIVED KANSAS CORPORATION COMMISSION** Plugged Due to Compliance Issue: Yes No

District: 03 **OCT 03 2013** *Frank Guilfoyle* (Technician)
 CONSERVATION DIVISION WICHITA, KS Form: District Plugging Report - _____