

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 28 TWP. 30S RGE. 13W E/W
Location as in quarters or footage from lines:
NE NW NE

Lease Owner Texas Energies Inc.
Lease Name Lemon A-1-28 Well No. _____
Office Address P O Box 947, Pratt, Ks. 67124
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 4/15/81
Plugging completed 4/21/81
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom T.D. 4460
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8	355	None
				5-1/2	4310	2267

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Made bottom hole plug back with sand to 3975 and set 5 sacks cement. Pulled 22 1/2 tension. Made shots at 3510, 3425, 3385, 3120, 2905, 2710, 2605, 2520. Checked hole and found mud at 2175. Shot again at 2380 and 2255. Worked pipe free. Pulled total of 66 joints. Squeezed hole with 15 sacks gel, 6 sacks hulls and 10 sacks gel. Released plug and displaced with 125 sacks 50/50 pos 4% gel 3% cc. Plugging completed.

4-28-81 APR 28 1981
RECEIVED
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of April, 19 81

My Commission expires:



Joan Kelso
Notary Public.