

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-97501-00-01 ⁰⁰⁵²⁶

LEASE NAME Ott

WELL NUMBER B-1

1650 Ft. from S Section Line

990 Ft. from W Section Line

SEC. 6 TWP. 34S RGE. 13 (E) (W)

COUNTY Barber

Date Well Completed 7-3-54

Plugging Commenced 4-11-96

Plugging Completed 4-22-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Oxy U.S.A.

ADDRESS 400 S. Main, Pratt, KS 67124

PHONE# (316) 672-5630 OPERATORS LICENSE NO. 5447

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-11-96 (date)

by Steve Middeltol (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Miss Depth to Top 4868 Bottom 4895 T.D. 4977

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	354	None
				5 1/2	5010	Approx 3300

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s Lay down rods and tubing, sand perfs back to 479-, dump 5sx cement with dump bailer, stretch and cut pipe at 3300, lay down casing, Allied pump 300 hulls, 10 jel, 50 cement, 10 jel, 100# CSH, 8 5/8 wiper plug, 100 cement, 60/40 6% jel, max press 150, TSTP 50

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy U.S.A.

STATE OF Kansas COUNTY OF Barber, ss.


Alan Vratil

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fac statements, and matters herein contained and the log of the above-described well as filed i the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Medicine Lodge, KS 67104



RECEIVED
SUBSCRIBED AND SWORN TO before me this 23 day of April, 19 96

Glenda Morrison
Notary Public

My Commission Expires: 10/14/98

FEB 23 1996

DRILLER'S LOG

CONSERVATION DIVISION
WICHITA, KS

Imperial Drilling Company, Inc.
903 Union National Bank Building
Wichita 2, Kansas

Ott No. 1
SW NW SE Sec. 6-34S-13W
Barber County, Kansas

Total Depth: 5010'

Commenced: June 13, 1954 Completed: 7-3-54 Elevation: 1861' R.B.
Production: 3,070,000 C.F.D

Contractor: R.C. Patton Company
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 354' W/250 sacks cement.
Set 5 1/2" casing at 5010' W/125 sacks cement.

Figures indicate bottom of formations:

Sand	90'		
Red Shale and Shells	280'		
Red Shale and Shells	320'		
Red Bed and Shells	360'		
Red Shale and Shells	810'		
Red Bed and Shells	1275'		
Red Shale and Shells	1630'		
Gray Shale, Shells and Salt	1825'		
Anhydrite and Shale	2005'		
Lime, Shells and Shale	2025'		
Anhydrite and Shale	2200'		
Lime and Shale	3492'		
Lime	3544'		
Lime and Shale	4375'		
Lime	4472'		
Lime and Shale	4748'		
Lime	4792'		
Lime and Shale	4868'		
Lime	4935'		
Lime and Shale	4966'		
Lime	5010'		
Total Depth	5010'		

		<u>TOPS</u>	
Toronto	4132'		(-2271)
Douglas Sand	4196'		(-2335)
Lansing	4303'		(-2442)
Mississippi	4868'		(-3007)
Rotary Total Depth	5010'		(-3149)

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL DRILLING COMPANY, INC.

By: Raymond E. Brown
Vice President

Subscribed and sworn to before me this 16th day of March, 1955.

My commission expires:

November 9, 1957

Marilyn E. Fox
Notary Public