


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 8 Twp 34S Rge. 13 (~~XX~~) (W)
Location as "NE/CNW&SW&" or footage from lines 200' W of W 1/2 NW NW
Lease Owner George R. Jones
Lease Name Blunk Well No. 3
Office Address 125 N. Market, Suite 1310, Wichita, KS 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 6, 1978 ~~NOX~~
Application for plugging filed January 18, 1978 ~~NOX~~
Application for plugging approved January 10, 1978 ~~NOX~~
Plugging commenced January 6, 1978 ~~NOX~~
Plugging completed January 6, 1978 ~~NOX~~
Reason for abandonment of well or producing formation Nonproductive

If a producing well is abandoned, date of last production -- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owen, Pratt, KS
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 5360 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface			362'	8 5/8"	354.21'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug at 360' with 35 sacks; plug and bridge at 40' with 12 sacks; 3 sacks in rathole.

RECEIVED
STATE CORPORATION COMMISSION

JAN 20 1978 1:20 PM

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, KS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GEORGE R. JONES

(~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George R. Jones
125 N. Market, Suite 1310
Wichita, KS 67202 (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of January, 1978

My commission expires March 12, 1978

Jeannine ReQua
Notary Public.

GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Blunk #3
 C-W/2-NW-NW Sec 8-34S-13W
 Barber County Kansas

Commenced: 12-21-77

Completed: 126-78

OPERATOR: GEORGE R. JONES

Depth		Formation	Remarks
From	to		
0	20	Sand	Ran 9 jts of 20# 8 5/8" csg set @ 362' Cemented w/ 300 sks Common 3% CC PD @ 3:50 a.m. 12-22-77
20	340	Red Rock-Redbed	
340	368	Shells-Clay	
368	1080	Shale-Shells	
1080	2120	Shale	
2120	2182	Lime-Shale	
2182	2545	Shale-Lime	
2545	2745	Lime	
2745	3135	Lime-Shale	
3135	3487	Lime	DRY & ABANDONED
3487	3675	Lime-Shale	
3675	5360	Lime	
	5360 - TD		

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.


GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 17th day of January, 1978.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.



RECEIVED
 STATE CORPORATION COMMISSION

JAN 20 1978

CONSERVATION DIVISION
 Wichita, Kansas