

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 9 Twp. 34 Rge. 13 (E) W (W)

Location as "NE/CNW&SW" or footage from lines C SW SW  
Lease Owner Prime Drilling Company et al  
Lease Name Donovan Well No. 1  
Office Address 814 Union Center - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 17, 1962  
Application for plugging filed February 17, 1962  
Application for plugging approved February 17, 1962  
Plugging commenced February 17, 1962  
Plugging completed February 17, 1962  
Reason for abandonment of well or producing formation No oil and/or gas found in commercial quantities  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4912 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	296'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 270'. Set Plug #1 at 270' with 20 sacks cement. Filled hole with extra Heavy rotary mud from Plug #1 to 40'. Set #2 at 40' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 27 1962  
2-23-62  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company  
Address 814 Union Center - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R R McNicol  
814 Union Center - Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of February, 19 62

My commission expires May 6, 1964  
Barbara E. Lewis Notary Public.

ROTARY DRILLING LOG

OPERATOR: Prime Drilling Company et al  
R. Donovan #1  
C SW SW Section 9-34S-13W  
Barber County, Kansas

CONTRACTOR: Prime Drilling Company  
COMMENCED: 1-28-62  
COMPLETED: 2-17-62

REMARKS: Set 8-5/8" surface casing at 296'. Cemented with 200 sacks pozmix.

FORMATIONS

Sand	9'
Shale and Lime	30'
Red Bed and Shale	530'
Shale	622'
Shale and Shells	1000'
Shale and Shells	1530'
Shale and Shells	1880'
Lime	2045'
Lime	2510'
Shale and Lime	2555'
Lime	2680'
Shale and Lime	2875'
Shale and Lime	3350'
Lime	3440'
Lime and Shale	3515'
Shale and Lime	3825'
Shale and Sand	3928'
Sand	3947'
Shale and Lime	4000'
Lime	4057'
Shale and Lime	4089'
Lime	4245'
Lime	4711'
Lime and Shale	4778'
Mississippi Lime	4790'
Lime	4854'
Lime	4895'
Lime and Chert	4912'

Rotary Total Depth (D & A) 4912'

We certify the above log is true and correct to the best of our knowledge and belief.

PRIME DRILLING COMPANY

*R. R. McNicol*

R. R. McNicol

500  
FEB 28 1962  
CARTER

ROTARY DRILLING LOG

CONTRACTOR: Prime Drilling Company  
 COMMENCED: 1-28-62  
 COMPLETED: 2-17-62

OPERATOR: Prime Drilling Company et al  
 R. Donovan #1  
 G 28 SW Section 2-34S-13W  
 Barber County, Kansas

REMARKS: Set 3-2 7/8" surface casing at 390'. Cemented with 200 sacks cement.

FORMATION

4913'	Lime and Chert
4895'	Lime
4878'	Lime
4790'	Mississippi Lime
4778'	Lime and Shale
4711'	Lime
4745'	Lime
4639'	Shale and Lime
4627'	Lime
4600'	Shale and Lime
3947'	Sand
3926'	Shale and Sand
3825'	Shale and Lime
3815'	Lime and Shale
3740'	Lime
3350'	Shale and Lime
2875'	Shale and Lime
2680'	Lime
2557'	Shale and Lime
2710'	Lime
2045'	Lime
1890'	Shale and Shells
1530'	Shale and Shells
1000'	Shale and Shells
823'	Shale
520'	Red bed and Shale
30'	Shale and Lime
0'	Sand

Rotary Total Depth (D & A) 4913'

We certify the above log is true and correct to the best of our knowledge and belief.

PRIME DRILLING COMPANY

*R. E. McNeil*

R. E. McNeil