

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 13 TWP. 20S RGE. 13W E/W
Location as in quarters or footage from lines:
SE SE NW

Locate Well
correctly on above
Section Platt.

Lease Owner F. G. Holl
Lease Name Means Well No. #1-13
Office Address 6427 East Kellogg, Wichita, Kansas 67207
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed June 29, 1983
Application for plugging filed June 29, 1983
Plugging commenced 9:00 AM, June 29, 1983
Plugging completed 10:45 AM, June 29, 1983
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Rick Lacey
Producing formation _____ Depth to top _____ bottom T.D. 4730'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10 3/4"	251'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud pumped through open ended drill pipe;
50 sacks at 720'; 50 sacks at 300'; 1/2 sack hulls,
plug and 15 sacks at 40'. 15 sacks in rathole.
Used 60/40 Pozmix, 2% gel and 3%cc.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas
(Address) 67579



SUBSCRIBED AND SWORN TO before me this 1st day of July, 19 83

Agnes D. Wurst
Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85

RECEIVED
STATE CORPORATION COMMISSION

JUL 05 1983

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- MEANS #1-13

Located: SE SE NW, Section 13-30S-13W, Barber County, Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 19, 1983

COMPLETED: June 29, 1983

TOTAL DEPTH: 4730'

LOG

CASING RECORD

0 - 20 Surface Soil
20 - 254 Clay, Red Bed
254 - 993 Shale, Red Bed
993 - 1520 Red Bed, Lime
1520 - 1900 Shale and Shells
1900 - 4115 Lime and Shale
4115 - 4240 Lime
4240 - 4600 Lime and Shale
4600 - 4730 Lime

Ran 6 joints new 10 3/4", 32# casing.
239.39' Pipe set at 251' K.B. Cemented
with 225 sacks 60/40 Pozmix plus 3% cc.
Plug down at 10:30 PM, 6-19-83, by Howco.

Plugged.

Deviation Surveys: 1 1/2° at 993'
3/4° at 2112'
1 1/2° at 4309'
1/2° at 4600'

RECEIVED
STATE DEPARTMENT OF CONSERVATION

JUL 05 1983

CONSERVATION DIVISION
Wichita, Kansas