

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED Form CP-4
Rev. 12-15-80
STATE CORPORATION COMMISSION

DEC 23 1981
12-23-81

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 12 TWP. 30 S RGE. 13 W E/W
Location as in quarters or footage from lines:
910 FNL -1850 FWL

Locate Well
correctly on above
Section Platt.

Lease Owner Texas Oil nad Gas Corporation
Lease Name Levens Well No. 1
Office Address Suite 300 - 200 W. Douglas
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed March 13, 1981
Application for plugging filed September 22, 1981
Plugging commenced December 17, 1981
Plugging completed December 21, 1981 12:15
Reason for abandonment of well or producing formation No gas.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well M. U. Leslie
Producing formation _____ Depth to top _____ bottom _____ T.D. 2900
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	278	None
				4 1/2	None	None
				2 7/8	2875	1708

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Halliburton pumped in 15 sacks of common cement.

Go shot tubing out - 1,708

Halliburton pumped in 15 Jell, 6 Hull, 10 Jell.

150 sacks common cement - 2% Jell, 3% C.C.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.
Clark R. Morgenstern (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Clark R. Morgenstern
Medicine Lodge, Mo
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of December 81

Jessie Hamilton
Notary Public.

My Commission expires: April 4, 1982.

KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 12 T. 30S R. 13W

FARM

Levens **GEOLOGICAL FILE**

LOC. 910' FNL & 1850' FR

COUNTY Barber

ROTARY TOTAL DEPTH 2,900'

COMM. March 2, 1980

COMP. March 7, 1980

CONTRACTOR H-30, INC. (Rig #5)

ISSUED March 13, 1980

CASING

10 3/4"

8 5/8" Set 8-5/8" at 278' cemented w/325 sxs cement ELEVATION 1,806' K.B.

5 1/2"

4 1/2"

2 7/8" Tubing set at 2,875' cemented w/200 sxs cement

Sand and Red Bed	302'
Red Bed and Shale	1,790'
Lime and Shale	1,843'
Shale and Lime	1,910'
Lime and Shale	2,125'
Shale and Lime	2,392'
Lime and Shale	2,565'
Shale and Lime	2,824'
Lime and Shale	2,900'
Rotary Total Depth	2,900'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas)
) ss:
County of Sedgwick)

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1981
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and Sworn to before me a Notary Public
in and for said county and state this 13th day of
March, 1980.



Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:
July 25, 1982