

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION


OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barber County. Sec. 31 Twp. 30 Rge. 13 ~~XX~~ (W)

Location as "NE¼NW¼SW¼" or footage from lines. NE¼
Lease Owner. Phillips Petroleum Company
Lease Name. Marjorie Well No. 2
Office Address. Box 779 - Great Bend, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed. March 14, 19. 46
Application for plugging filed. November 29 19. 50
Application for plugging approved November 30 19. 50
Plugging commenced. December 21 19. 50
Plugging completed. December 22 19. 50
Reason for abandonment of well or producing formation.
Uneconomical to operate - gas completed
If a producing well is abandoned, date of last production. 19. _____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes



Locate well correctly on above
Section Flat

Name of Conservation Agent who supervised plugging of this well. C. D. Stough
Producing formation. Maquoketa Depth to top. 4522 Bottom. 4538 Total Depth of Well. 4538 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Anhydrite	Dry	744	830	8 5/8"	824'	None
Maquoketa	Gas	4522	4538	5 1/2"	4566'	3207'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Well was originally drilled to 4550' 6" and plugged back with cement to 4538' in 1946'. Filled hole from 4538' to 4465' with 5 sx. cement. Mudded hole from 4465' to 250'. Dumped 15 sx. cement from 250' to 200'. Mudded hole to bottom of cellar. Dumped 10 sx. cement from bottom of cellar to surface.

RECEIVED
STATE CORPORATION COMMISSION
DEC 27 1950
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. A. W. Mallow
Address. Box 779 - Great Bend, Kansas.

STATE OF KANSAS, COUNTY OF BARTON, ss.
A. L. Rhodes (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Rhodes
Box 779 - Great Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of December, 19. 50

My commission expires November 18, 1953

Joseph M. Beal
Notary Public.

PLUGGING
FILE SEC 31 T 30 R 130
BOOK PAGE 46 LINE 8

Formation Record

Lease Marjorie

Well No. 2

FROM	TO	Formation	REMARKS
0	390	Sand, Shells and Red Bed	Elevation 1835' D.F.
390	715	Red Bed	
715	836	Red Bed and Anhydrite	
836	1236	Red Bed and Grey Shale	
1236	1460	Shale and Shells	
1460	1622	Shale and Shells	
1622	1700	Lime and Shale	
1700	1880	Lime and Shale	
1880	2055	Lime	
2055	2140	Lime	
2140	2195	Lime and Shale	
2195	2240	Lime and Shale	
2240	2350	Shale and Shells	
2350	2405	Lime and Shale	
2405	2410	Lime	
2410	2524	Lime and Shale	
2524	2742	Lime and Shale	
2742	2980	Lime and Shale	
2980	3048	Shale, Lime and Shells	
3048	3068	Lime and Shale Breaks	
3068	3298	Lime and Shale	
3298	3362	Lime and Shale	
3362	3488	Lime and Shale	
3488	3592	Lime and Shale	
3592	3763	Lime and Shale	
3763	3851	Lime, Shale and Shell	
3851	3892	Shale	
3892	3991	Lime and Shale	Top LKC 3938' D.F.
3991	4064	Lime	
4064	4140	Shale and Lime	
4140	4168	Lime and Shale Breaks	
4168	4199	Lime and Shale	
4199	4227	Lime and Shale	
4227	4240	Lime and Shale Breaks	
4240	4269	Lime and Shale	
4269	4332	Lime	
4332	4406	Lime	
4406	4424	Lime and Shale	
4424	4450	Lime, Shale and Chat	Top Cherty Conglomerate 4427'
4450	4476	Lime and Shale	Top Mississippi 4435'
4476	4518	Shale	Top Kinderhook 4467'
4518	4536	Lime and Shale	Top Meisner Sand 4520'
4536	4540	Lime	Top Maquoketa 4522'
4540	4550'6"	Lime	Top PBT 4538'

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1950

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC 31 T 30 R 13
BOOK PAGE 46 LINE 8