

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15,007-20,791-00-00 (of this well) 1/187
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TXO Production Corp. OPERATORS LICENSE NO. 5171

ADDRESS 155 N. Market, Suite 1000, Wichita, KS. 67202 PHONE # (316) 269-7600

LEASE (FARM) MEANS "B" WELL NO. 1 WELL LOCATION 660' FEL COUNTY Barber

SEC. 11 TWP. 30S RGE. 13 ~~XXXX~~(W) TOTAL DEPTH 3217' PLUG BACK TD 2980'

Check One:

OIL WELL _____ GAS WELL X D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 320' CEMENTED WITH 300 SACKS

CASING SIZE 2-7/8" SET AT 3015' CEMENTED WITH 250 SACKS

PERFORATED AT 2762-66' Indian Cave

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Plug perfs w/ 5 sxs sand + 5 sxs cement

w/ dump bailer. Cut casing @ ± 2000'. POOH w/ casing. Plug surface pipe w/ 5 sxs hulls, 10 sxs

gel + 100 sxs Econolite cement.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? YES
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry W. Collins PHONE # (316) 886-5605

ADDRESS P.O. Box 125-B, R.R. #1, Medicine Lodge, KS. 67104

PLUGGING CONTRACTOR Clarke Oilfield Services LICENSE NO. 5105 6/87

ADDRESS 107 W. Fowler, Medicine Lodge, KS. 67104 PHONE # (316) 886-5605

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jeffrey S. Childs
(Operator or Agent)

DATE: March 5, 1987

①



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HENLEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

JUN 13 '87

EXPIRES

March 13, 1987

WELL PLUGGING NOTICE

Means "B" #1
3450'FSL 660'FEL
Sec. 11-30S-13W
Barber County

TXO Production Corporation
155 N. Market, Ste. 1000
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging

DIST. #1 302 West McArtor, Dodge City, KS 67801 (316) 226-6760

five days prior to plugging the well (KAR-82-3-113).