



15-007-30212-00-00

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 26 1966  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Fred Bennett of Tennaco Oil Company has this date requested permission to plug the following described well:

Mr. Bennett guarantees payment of the plugging fee.

Operator's full Name: Tennaco Oil Company

Complete Address: 2000 Classen Center, N. Bldg., Oklahoma City, Okla.

Lease Name: L. M. Lee "A" Well No. # 2

Location: C SW NW Sec. 9 Twp. 30 Rge. 15(E)(W) W

County Barber Total Depth 4700' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Bennett was instructed to plug the well as follows:  
305' of 8 5/8" surface pipe, cement circulated with 235 sacks.  
Fill hole with drilling mud to 290', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent