

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.


OPERATOR TXO PRODUCTION CORP. API NO. 15-OWWO 15-005-00588-00-01  
 ADDRESS 200 W. Douglas, Suite 300 COUNTY Barber  
Wichita, KS 67202 FIELD X Wildcat (OWWO) NURSE NW  
 \*\*CONTACT PERSON Harold R. Trapp LEASE Hamilton  
 PHONE 265-9441

PURCHASER Delhi WELL NO. Hamilton "A" #1 OWWO  
 ADDRESS 2150 Fidelity Union Tower WELL LOCATION SE NE  
Dallas, TX 75201 1980 Ft. from North Line and  
 660 Ft. from East Line of  
 the 34 SEC. 30S TWP. 13W RGE.

DRILLING CONTRACTOR H-30, Rig #5  
 ADDRESS 251 N. Water  
Wichita, KS 67202

PLUGGING CONTRACTOR N/A  
 ADDRESS \_\_\_\_\_

TOTAL DEPTH 4110' PBDT 4070'  
 SPUD DATE N/A DATE COMPLETED 1-21-81  
 ELEV: GR 1838 DF KB 1845



WELL PLAT  
~~(XXXXXX)~~  
 or (Full) Section - Please indicate.

KCC   
 KGS   
 PLUL

DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(XXX)~~ TOOLS  
 Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface run by	original	operator					
Production		2-7/8"	6.5#	4101	100 gals mud flush, 25 sxs Scavenger &	40	bbls 2% KCl, sxs Class "A"

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A	2 JSPF (7 h.)	Douglas	3820-23'
TUBING RECORD					
Size	Setting depth	Packer set at			
N/A	N/A	N/A			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
Dumped 250 gals acetic acid + 13 bbls 1% HCl wtr	3820-23'
Acidized w/250 gals 15% DeMud acid w/fluorosurfactant & stabilizer	3820-23'

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 NOV 17 1981 11-17-81

TEST DATE:		PRODUCTION		FORMATION COND.	
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Oil	Gas	Water	A.P.I. Gravity
11-2-81	flowing	N/A	1080 MCFD	N/A	N/A
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		N/A	1080 MCFD	N/A	N/A
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		
Sold			3820-23'		

\*\* The person who can be reached by phone regarding any questions concerning this information.  
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

FIELD: Wildcat (OWWO)

Name of lowest fresh water producing stratum Unknown Depth N/A  
 Estimated height of cement behind pipe Circulated to Surface

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
LOG TOPS				
Foraker	2757	-911		
Onaga	2824	-978		
Indian Cave	2834	-988		
Wabaunsee	2874	-1028		
Stotler	3014	-1168		
Howard	3212	-1366		
Topeka	3395	-1549		
Oread	3679	-1833		
Heebner	3759	-1913		
Toronto	3771	-1925		
Douglas Grp.	3784	-1938		
Brown Lime	3932	-2086		
Lansing	3954	-2109		
RTD	4110			
PBD	4070			
Ran O.H. Logs				
No DSTs.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

**A F F I D A V I T**

STATE OF Kansas, COUNTY OF Sedgwick SS,

Harold R. Trapp OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS District Geologist FOR TXO Production Corp. OPERATOR OF THE Hamilton LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. "A"#1 OWWOON SAID LEASE HAS BEEN COMPLETED AS OF THE 2nd DAY OF November 19 81, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Harold R. Trapp

SUBSCRIBED AND SWORN TO BEFORE ME THIS 10<sup>th</sup> DAY OF November 19 81

**PAMELA S. JOLLIFF**

STATEWIDE  
NOTARY PUBLIC  
Harvey County, Ka.

Pamela S. Joliff  
NOTARY PUBLIC

My Appt. Expires 9/14/83  
MY COMMISSION EXPIRES

Pamela S. Joliff  
9/14/83