

RECEIVED

NOV 02 2001

KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-007-22,412-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. *6/02*
F.G. Holl Company, L.L.C.

WELL OPERATOR _____ KCC LICENSE # 5056

ADDRESS 6427 E. Kellogg, P.O. BOX 780167 (owner/company name) CITY Wichita (operator's)

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # () (316) 684-8481

LEASE LAWRENZ WELL# 1-11 SEC. 11 T. 30s R. 13 (East/West)

C S/2 - SW - NW SPOT LOCATION/QQQQ COUNTY Barber

2970 FEET (in exact footage) FROM (S) N (circle one) LINE OF SECTION (NOT Lease Line)

4620 FEET (in exact footage) FROM (E) W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL _____ D&A _____ SWD/ENHR WELL _____ DOCKET# _____

CONDUCTOR CASING SIZE 13 3/8" SET AT 235'KB CEMENTED WITH 225 SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1036'KB CEMENTED WITH 350sx SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4780'KB CEMENTED WITH 225sx SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4318' - 4330' Marmaton, 4529'-4534' Viola

ELEVATION 1838'/1847' T.D. 4800' P.B.T.D. 4767' ANHYDRITE DEPTH N/A
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, Cement and plug according to KCC regulations

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob Long PHONE# () (316) 995-3171 (O)/793-0915 (Cell)

ADDRESS P.O. BOX 158 City/State Belpre, KS. 67519

PLUGGING CONTRACTOR Quality Well Service, Inc. KCC LICENSE # 31925 *8/02*

ADDRESS 249 Beth Drive, Sterling, KS. 67579 (company name) PHONE # () (316) 278-2476 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Not known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11/01/2001 AUTHORIZED OPERATOR/AGENT: Franklin B. Greenbaum
(signature)
(Exploration Manager)

STERLING DRILLING COMPANY

BOX 129
STERLING, KANSAS 67579
(316) 278-2131

SAMPLE LOG - - - - - LAWRENZ #1-11
Located C S/2 SW NW, Section 11-30S-13W,
Barber County, Kansas

OWNER: F. G. HOLL COMPANY
ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED; March 19, 1993
COMPLETED: March 31, 1993

RECEIVED

NOV 02 2001

TOTAL DEPTH; 4800' K.B. Driller
4798' K.B. Logger

KCC WICHITA

LOG

0' - 75' Surface Soil and Sand
75' - 235' Red Bed
235' - 500' Shale and Red Bed
500' - 931' Lime and Shale
931' - 1040' Shale and Red Bed
1040' - 1330' Shale
1330' - 4800' Lime and Shale

CASING RECORD

Spud at 9:15 AM, 3-19-93, Drilled 235' of 17 1/2" hole. Ran 5 joints of 13 3/8", 48# new casing. 222.41' pipe set at 235' K.B. Cemented with 225 sacks of 60/40 Pozmix with 2% gel and 3% cc. Plug down at 4:00 PM, 3-19-93, by Allied with returns to surface.

Lost circulation at 913'. Reamed 7 7/8" hole to 12 1/4" hole from 235' to 1040'. Ran 23 joints of 8 5/8", 23# new casing. 1023.79' pipe set at 1036' K.B. Cemented with 350 sacks Lite with 1/4# flocele per sack, followed with 200 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 1:45 PM, 3-21-93 by Howco. Baskets on joints 1 and 20. Good returns to surface.

Ran 112 joints 4 1/2", 10.5# new and used casing (495.49' used). Total 4772.15' pipe set at 4780' K.B. Cemented with 20 bbl. salt flush and 500 gallons Superflush, followed with 100 sacks Lite cement, followed with 125 sacks of F. G. Holl mix. Plug down at 12:15 AM, 3-31-93, by Howco. Centralizers on Joints 1, 5, 10, 15 and 19. Shoe joint 13.08' long. Plugged rathole with 15 sacks.

DEVIATION SURVEYS

0 degree at 505'; 3/4 degree at 746'; 1 1/2 degree at 1040'
1/2 degree at 3794'; 3/4 degree at 4340'



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
6427 East Kellogg
Wichita, KS 67207

November 16, 2001

Re: LAWRENZ #1-11
API 15-007-22412-00-00
S2SWNW 11-30S-13W, 2970 FSL 4620 FEL
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-8888