

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 007 - 20475 - 00 - 01 (of this well)

Operator's Full Name Texas Tol & Gas Corp.

Complete Address 200 W. Douglas, Suite 300, Wichita, Ks. 67202

Lease Name Bauman "A" (OWWO) Well No. 1

Location 180' NE SW SW SE Sec. 34 Twp. 31 Rge. 12 (E) (W) X

County Barber Total Depth 4552

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Clarke Corp.

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 10:45 Am Day 11 Month 9 Year 1979

The above well was plugged as follows:

265' 8 5/8" casing w/250 sax cement. 4 1/2" casing set at 4351' w/150  
sax cement. Plug back to 4317' - Preforated at 4258' to 4278' - Sand back  
to 4275' - Top sand w/4 sax mixed cement w/ dump bailer. Pull 2825' 4 1/2"  
casing. Allied mixed & pumped 8 sax hulls - 20 sax gel - Release plug, mixed  
& pumped 100 sax 50/50 posmix cement w/4% gel to top of casing - Shut in  
w/700# pressure.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 14 1979

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

DATE 9-14-79  
INV. NO. 0442-W