

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1964

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Sierra Petroleum Co., Inc.

Complete Address: 1015 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Updegraff Well No. # 1

Location SW SW NE Sec. 34 Twp. 31 Rge. 12 (E) (W) W

County Barber Total Depth 4355

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 12:30 PM Day 26th Month Sept. Year 1964

The Above well was plugged as follows:

165' of 8 5/8" surface pipe, cemented with 125 sacks. 4354' of 4 1/2" long
string, cemented with 125 sacks. Plug back to 4337'. Top perforation
slot 4289'. Bottom of the hole was sanded to 4275', and cemented with
3 sacks. Fluid in the hole was bailed down to 250', bridge plug was set
on fluid at 250', and 10' of rock bridge, and cemented with 40 sacks,
bringing the top of the cement to 92', in the surface pipe. Hole was
filled with mud to 40', and 10' of rock bridge, and cemented with 10 sacks
to the base of the cellar. 3615' of 4 1/2" long string was recovered from
the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging SupervisorDATE 9/28/64INV. NO. 9880-W