

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 19 1966  
12-19-66  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Ferguson Oil Company

Complete Address: 1505 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Walker Well No. # 1

Location C SW NE Sec. 28 Twp. 30 Rge. 15 (E) (W) W

County Barber Total Depth 4443'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Walters Drilling Company

Address: 400 Insurance Bldg., Wichita, Kansas License No.     

Operation Completed: Hour 12:45AM Day 16th Month Dec. Year 1966

The Above well was plugged as follows:

63' of 13 3/8" surface pipe, cement circulated with 80 sacks. 797' of 8 5/8"  
surface pipe, cement circulated with 500 sacks. Hole was filled with drilling  
mud to 300', 1st cementing plug, bridged with 2 sacks of dry cement, and 1/2  
sack of hulls on fluid at 300', and cemented with 23 sacks. Hole was filled  
with drilling mud to 40', 2nd cementing plug, bridged with 1 sack of dry cement,  
and 1/2 sack of hulls on fluid at 40', and cemented with 9 sacks to the base of  
the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Ebling  
Well Plugging Supervisor

DATE 12/19/66  
INV. NO. 4473-W