

CP3

State of Kansas



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date 4 August, 1958, authorized the following plugging operation:

Operator's Full Name: Honaker Davis Oil Co.

Complete Address: 1008 Lakin, Great Bend, Kans.

Lease Name: Walker "B" Well No. 1

Location: CNW SW Sec. 31 Twp. 30 Rge. 15 (E) (W) X

County: Barber Total Depth: 4990

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Sand to 4770' and dump 5 sack cement with bump bailer. Pull pipe
to 1700' and circulate heavy mud. Pull pipe. Heavy mud to
350', set rock bridge and dump 20 sack cement top bridge. Heavy
mud to 40. Rock bridge and 10 sack cement to base of cellar.

Very truly yours,

Signed: [Signature]
Conservation Division Agent

RECEIVED
 STATE CORPORATION
 AUG 23 1958
 8-29-58
 CONSERVATION DIVISION
 Wichita, Kansas