

R

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

CPB

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Barber

Location: CNW SW Sec. 31 Twp. 30 Rge. 15 (E) (W) X

Name of Field: \_\_\_\_\_ Total Depth: 4990

I have this date completed supervision of plugging of:

Lease Name: Walker "B" Well No. 1

Operator's Full Name: Honaker Davis Oil Co.

Complete Address: 1008nLakin, Great Bend, Kans.

Plugging Contractor: West Supply

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No X

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 6 PM Day 15 Month Aug Year 1958

The above well was plugged as follows:

406' of 8 5/8" surface casing circulated with cement. Perf 4770 to 70.  
Hole was sanded to 4770' with 5 sack cement dumped with dump bailer. Pulled  
55 jts. and circulated heavy drilling mud. Pulled all oil production pipe.  
Heavy mud to 350' with rock bridge set and 20 sack cement dumped. Heavy  
mud to 40'. Rock bridge set with 10sack cement to base of cellar.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

PLUGGING  
FILE SEC. 31 T. 30 R. 15W  
BOOK PAGE 112 LINE 21