

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 2 1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Livingston Oil Company & Gayle Toland

Complete Address: Box 1797, Tulsa, Oklahoma

Lease Name Massey "C" Well No. # 1

Location NE NE NE Sec. 34 Twp. 30 Rge. 15 (E) (W)W

County Barber Total Depth 4305'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950 El Dorado, Kansas License No. 547

Operation Completed: Hour 5:00PM Day 31st Month March Year 1965

The Above well was plugged as follows:

711' of 8 5/8" surface pipe, cemented with 375 sacks. 4291' of 5 1/2"  
long string, cemented with 200 sacks. This is an open hole. Bottom  
of the hole was sanded to 4280', and cemented with 5 sacks. 3180' of  
5 1/2" long string was recovered from the hole. Hole was filled with  
mud to 300', and 10' of rock bridge, and cemented with 25 sacks.  
Hole was filled with mud to 40', and 10' of rock bridge, and cemented  
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/2/65

INV. NO. 921-W