

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 007 - 20807 - 00 - 00 (of this well)

Operator's Full Name National Oil Co.

Complete Address 200 W. Douglas, Suite 800, Wichita, Ks. 67202

Lease Name Lemon Well No. 1

Location C NE NW Sec. 9 Twp. 30S Rge. 13 (E) (W)

County Barber Total Depth 4700

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 67524 License No. 683

Operation Completed: Hour 5:30 Pm. Day 13 Month 2 Year 1980

The above well was plugged as follows:

280' 10 3/4" casing, 5 1/2" casing set at 4695' w/150 sax cement. Plug  
back to 4590'-Preforated at 4514' to 4517'-Sand back to 4500'-Top  
sand w/5 sax mixed cement w/dump bailer. Pull 3400' casing. Allied  
mixed & pumped 8 sax hulls-30 sax gel-150 sax 50/50 posmix cement  
w/4% gel & 3% cc to top of casing. Shut in w/"0" pressure.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 15 1980  
CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**

DATE 2-15-80

INV. NO. 1534-w