

He
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Leo J. Dreiling

Complete Address: Victoria, Kansas

Lease Name Knackstedt Well No. # 1

Location C SE SW Sec. 6 Twp. 30 Rge. 13 (E) W

County Barber Total Depth 4622

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractors: L. J. Dreiling & Sons Inc.

Address: Victoria, Kansas License No.

Operation Completed: Hour 2:30AM Day 28th Month Sept. Year 1963

The Above well was plugged as follows:

858' of 8 5/8" surface pipe, cemented with 475 sacks. Fluid level in
the hole was at 230', 1st cementing plug was set at 230', bridged with
1/2 sack hulls, cemented with 25 sacks. Hole was filled with drilling
mud to 40', 2nd cementing plug, bridged with 1/2 sack hulls, cemented
with 10 sacks to base cellar. Rat hole bridged and cemented with 2
sacks. Mouse hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 9/30/63
INV. NO. 9817-W

Signed: Audie Elving
Well Plugging Supervisor