

DISTRICT CONSERVATION AGENT'S REPORT

*Handwritten initials/signature*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 46-8

LOCATION ~~22E/4~~ CS/2 NE

SEC. 31 TWP. 30 RGE. 13-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Majoria

Operator Phillips Petro. Co. Address Box #779 - A. Bend - Kans.

Field \_\_\_\_\_ County Barber

Total Depth 4349 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/2" - 830 ft. Circulated with cement.  
5/8" casing set at 4539 ft. & cemented - Plugged back to  
4538 ft with cement - Filled hole with shot to 4500 ft.  
Dumped 3 sacks of cement at 4500 ft - Shot off & pulled  
the 5/8" casing - mud to 250 ft. Set Rock Bridge  
& 15 sacks of cement at 250 ft. Mud to 30 ft.  
Plug & 10 sacks cement at the surface.  
West Supply Co. Plugging Contractors*

**PLUGGING**  
DEC 29 1950  
FILE SEC. 132  
CONSERVATION DIVISION  
Wichita, Kansas

C. H. Stover  
District Conservation Agent

Date 12-23-50