

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 130 S. Market, Room 2078  
 Wichita, KS 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-007-21,963-0000

LEASE NAME Ricke Estate

WELL NUMBER 4

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 12 TWP. 32 RGE. 11W (E) or (W)

COUNTY Barber

Date Well Completed         

Plugging Commenced 4-18-97

Plugging Completed 4-23-97

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Hummon Corporation

ADDRESS 950 N. Tyler Rd. Wichita, KS 67212-3240

PHONE# (316) 773-2300 OPERATORS LICENSE NO. 5050

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          Steve Middleton (date)

by          (KCC District Agent's Name).

Is ACO-1 filed?          if not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.O. 3780'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	224'	none
				5 1/2	3779'	3014'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from          feet to          feet each s  
Sanded off bottom to 3546' & ran 5 sks cement. Shot casing at 3223' & 3014'. Came loose at 3014'. Pulled csg to 600'. Load hole w/3 sks gel and pumped 50 sks cement @ 600'. Pulled casing to 250', pumped 50 sks cement. Pulled all casing & topped with 20 sks cement. Plugging complete. 60/40 poz 6% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 1529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hummon Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fac-  
 statements, and matters herein contained and the log of the above-described well as filed t  
 the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 5th day of May, 19 97

*James Humphrey*  
 Notary Public

My Commission Expires:         



RECEIVED  
 KANSAS  
 CORP  
 1997 MAY 5 P 12:55  
 5-6-97