

LEASE NAME Ricke Estate

WELL NUMBER 1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 12 TWP. 32 RGE. 11W (E) or (W)

COUNTY Barber

Date Well Completed         

Plugging Commenced 5-6-97

Plugging Completed 5-9-97

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Hummon Corporation

ADDRESS 950 N. Tyler Rd., Wichita, KS 67212-3240

PHONE# (316) 773-2300 OPERATORS LICENSE NO. 5050

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)  
 by          (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3800'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	221'	none
				5 1/2	3799'	2319'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from          feet to          feet each s.  
Pulled all rods and tubing. Sanded bottom to 3573' and ran 5 sks cement. Shot at 2680', 2578', 2413', 2319'. Pipe came loose at 2319'. Pulled up to 620' load hole w/fresh water. Pumped 3 gel spacer. Spot 50 sks cement. Pulled out rest of pipe. Circulated 20sks cement to surface from 40'. Plugging complete. 60/40 poz 6% gel. sx

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hummon Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed t the same are true and correct, so help me God.


(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 97

*Irene Herzberg*  
 Notary Public

My Commission Expires:         



RECEIVED  
 TRANSCRIPTIONS  
 1997 MAY 21 10:35  
 5-21-97