

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-22,115-00-00

LEASE NAME Cargill

WELL NUMBER 1

3300 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 34 TWP. 31SRGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed 1-19-86

Plugging Commenced 1-19-86

Plugging Completed 1-19-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mull Drilling Company, Inc.

ADDRESS P.O. Box 2758, Wichita, KS 67201

PHONE#(316) 264-6366 OPERATORS LICENSE NO. 5144

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? #1, Dodge City, KS

Is ACO-1 filed? To be filed. If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0'	260'	8-5/8"	253.22'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged with 50 sacks cement at 600'; 40 sacks cement at 290';
solid bridge plug and 10 sacks cement at 40'; 15 sacks cement in rat hole;
10 sacks cement in mouse hole (60-40 Pozmix Cement, 6% Gel, 3% Calcium Chloride)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. _____

Address 600 Colorado Derby Bldg., Wichita, KS 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John D. Knightley, Agent (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) [Signature]


(Address) John D. Knightley, Agent

221 S. Broadway, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 11th day of February, 1986

[Signature]
Notary Public

My Commission Expires: March 12, 1987



STATE CORPORATION COMMISSION

FEB 18 1986 2-18-86

Form CP-4
Revised 08-84

CONSERVATION DIVISION
Wichita, Kansas

Mull Drilling Company, Inc.
P.O. Box 2758
Wichita, Kansas 67201

- Cargill #1
C E/2 SW NE Sec. 34-31S-12W
Barber County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: January 9, 1986
Completed: January 19, 1986

Drillers Log

Red Bed & Shale	263
Red Bed	745
Shale & Shells	1762
Shale	2055
Shale & Shells	2760
Shale & Lime	2970
Lime & Shale	3195
Shale & Lime	3360
Lime & Shale	3490
Shale & Lime	3620
Lime	4740 RTD

Casing: 260' 8-5/8" cemented with 175 sacks Class A Cement,
2% Gel, 3% Calcium Chloride.

RECEIVED
STATE CORPORATION COMMISSION

FEB 18 1986

CONSERVATION DIVISION
Wichita, Kansas