


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 34 Twp. 31S Rge. 12 (W)
Location as "NE/CNW&SW" or footage from lines. SW/4 SW/4 NE/4
Lease Owner Mull Drilling Company
Lease Name E. D. Updegraff Well No. 1
Office Address 6405 East Kellogg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 4, 1957 19
Application for plugging filed April 4, 1957 19
Application for plugging approved April 4, 1957 19
Plugging commenced April 4, 1957 19
Plugging completed April 4, 1957 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation None Depth to top Bottom Total Depth of Well 4355 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 200 feet. Bottom plug set at 200' using 25 sacks of cement. Top plug set at 30' using 10 sacks of cement and 1/2 sack of hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Iron Drilling Company
Address 1206 Philtower Building, Tulsa 3, Oklahoma

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
R. James Gear, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. James Gear

SUBSCRIBED AND SWORN TO before me this 15th day of April, 1957 (Address)

My commission expires January 28, 1961 Ethel Zimmerman Notary Public.

PLUGGING
FILE SEC. 34 T. 31 R. 12W
BOOK PAGE 4 LINE 16

RECEIVED
STATE CORPORATION COMMISSION

APR 16 1957 4-10-57
CONSERVATION DIVISION
Wichita, Kansas

Hull Drilling Co., Inc. DRILLING RECORD

Well: Updegraff No. 1
 SW SW NE Sec. 34-318-12W
 Barber County, Kansas

Casing Record:

165' of 8-5/8" Surface Pipe
 cemented with 125 sacks.

Work Commenced: 3-16-57
 Drilling Commenced: 3-18-57
 Drilling Completed: 4- 4-57
 Work Completed: 4- 8-57

No Production - Dry Hole

WELL LOG

Surface soil	0	to	20
Sand	20	to	135
Sand & shale	135	to	165
Red bed	165	to	400
Red bed, shale & lime shells	400	to	1065
Shale & shells	1065	to	1265
Lime & shale	1265	to	1630
Lime	1630	to	1695
Lime & shale	1695	to	2508
Lime	2508	to	2610
Lime & shale	2610	to	2840
Lime	2840	to	2920
Lime & shale	2920	to	3200
Lime	3200	to	3230
Lime & shale	3230	to	3557
Lime	3557	to	3590
Shale & lime streaks	3590	to	3705
Lime & shale	3705	to	3744
Lime	3744	to	4020
Lime & shale	4020	to	4045
Lime	4045	to	4285
Miss. lime	4285	to	4303
Cherty Miss. lime	4303	to	4323
Lime	4323	to	4355 T.D.

CERTIFICATION

State of Oklahoma)
 County of Tulsa) ss

PLUGGING			
FILE	SEC 34	T 31	R 12W
BOOK	PAGE 4	LINE 16	

I, J. L. Stackpole, Employee of Iron Drilling Company,
 Certify that the accompanying is a true and correct log of the above
 described well.

Subscribed to and Sworn before me this 22nd day of April, 1957.

My commission expires February 28, 1960

J. L. Stackpole

A. Michal

 Notary Public