

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

R

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 34 Twp. 31 Rge. 12 (E) (W) X  
Location as "NE/CNW&SW&" or footage from lines SW SW NE  
Lease Owner Sierra Petroleum Co., Inc.  
Lease Name Updegraff Well No. #1  
Office Address 1015 Wichita Plaza Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 9-23-64 19  
Plugging completed 9-26-64 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation Depth to top Bottom Total Depth of Well 4355' Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
						3617.82'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made plug back with sand to 4275', mixed and ran 3 sacks cement with dump baler.  
Mudded hole to 250' - sat 20' rock bridge, mixed and ran 40 sacks cement thru  
dump baler. Mudded hole to 40' and sat 10' rock bridge. Mixed and dumped 10  
sacks cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 29 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.  
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.  
Box 364, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of September, 1964

My commission expires 24 October 1964

Sidney D. Miller  
Notary Public.


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company- MULL DRILLING CO.  
Farm- Updegraff No. 1

SEC. 34 T. 31 R. 12W  
SW SW NE

Total Depth. 4355'  
Comm. 3-18-57 Comp. 4-4-57  
Shot or Treated.  
Contractor.  
Issued. 5-11-57

County Barber  
KANSAS



CASING:  
8 5/8" 165' w/105' sr. con.

Elevation. 1791' RB

Production Day

Figures Indicate Bottom of Formation

surface soil	0
sand	135
sand-shale	165
red bed.	200
red bed-shale-lime	
shells	1065
shale-shells	1265
lime-shale	1630
lime	1695
lime-shale	2508
lime	2610
lime-shale	2840
lime	2920
lime-shale	3200
lime	3330
lime-shale	3557
lime	3590
shale-lime str.	3705
lime-shale	3744
lime	4020
lime-shale	4045
lime	4285
Mississippi lime	4303
cherty Mississippi	
lime	4323
lime	4355
Total Depth	

TOPS: Scout	
Elgin	3399
Douglas	3586
Lansing	3716
Mississippi	4236

**RECEIVED**  
STATE CORPORATION COMMISSION

SEP 21 1964

CONSERVATION DIVISION  
Wichita, Kansas