

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Barber County. Sec. 2 Twp. 34 Rge. 13 (X) (W)

Location as "NE/CNW/SW" or footage from lines NE NW SE  
Lease Owner Messman-Rinehart Oil Co., and Barbara Oil Co., et al  
Lease Name Holmes "A" Well No. 1  
Office Address 518 Petroleum Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed July 30, 1957 19  
Application for plugging filed July 31, 1957 19  
Application for plugging approved August 1, 1957 19  
Plugging commenced July 30, 1957 19  
Plugging completed July 30, 1957 19  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Box 8, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	246'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy rotary mud to 240'. Halliburton plug, hulls and 20 sacks cement set through the drill pipe to 240'. Filled with rotary mud to 35'. Halliburton plug, 1/3 sack hulls and 10 sacks cement at 35'.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Messman-Rinehart Oil Company  
Address 518 Petroleum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland  
518 Petroleum Bldg, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of August, 1957

My commission expires September 5, 1960

Elaine M. Malone  
Notary Public, Kansas

PLUGGING  
FILE SEC 2 T. 34 R. 13W  
BOOK PAGE 32 LINE 45

97.57 AUE 7 1957  
RECEIVED: CONSERVATION DIVISION  
WICHITA, KANSAS

NO. 1 HOLMES "A"

Well Record

Location:	NE NW SE 2-34S-13W Barber County, Kansas	Commenced:	July 9, 1957
Operator:	Messman-Rinehart Oil Company 518 Petroleum Bldg., Wichita, Kansas	Completed:	July 30, 1957
Contractor:	Messman-Rinehart Oil Company 518 Petroleum Bldg., Wichita, Kansas	Elevation:	1580 KB

Casing Record: 8 5/8" @ 246' w/175 sacks cement.

\* \* \* L O G \* \* \*

Red Rock & shale	497	
Shale & Red Bed	900	
Shale-shells	1415	
Shale-shells & salt	1735	
Anhydrite	1750	
Shale w/strks Anhydrite	1800	
Lime-shale	2075	
Shale-lime	2144	
Lime-shale	2427	
Shale-lime	2515	
Lime-shale	2838	
Shale-lime	2979	
Lime-shale	3175	
Shale-lime	3194	
Lime-shale	4030	
Lime	4510	
Lime-shale	4609	
Lime	4670	
Lime-chert	4692	
Lime	4721	
Lime-shale-chert	4775	
Lime	4822	
Lime-chert	4893	
Lime-shale	4923	
Shale	4967	
Lime-shale	4982	
Lime-chert	5031	
Lime-shale-chert	5071	
Lime-shale	5084	
Shale-sand	5098	
Sand-shale	5164 R.T.D.	

	Electric log tops:
	Elgin 3581 (-2001)
	Heebner 3840 (-2260)
	Lansing 4004 (-2424)
	Miss. 4649 (-3069)
	Viola 4966 (-3386)
	Simpson 5075 (-3495)
	Simpson Sd. 5090 (-3510)

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland  
J. A. Gilliland

Subscribed and sworn to before me  
this 5th day of August, 1957.

Elaine M. Malone  
Notary Public

My Commission Expires: September 5, 1960

<b>PLUGGING</b>	
FILE	SEC 2 T 34 R 13W
BOOK	PAGE 32 LINE 45

RECORDED  
STATE OF KANSAS  
AUG 10 1957  
COMM. DIVISION  
WICHITA, KANSAS