


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 31 Twp. 30 Rge. 15 (E) W (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines C NW SW  
Lease Owner Honaker-Davis Drlg. Co.  
Lease Name Walker "B" #1 Well No. \_\_\_\_\_  
Office Address Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 8-5-58 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 8-15-58 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4990 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	406'	none
				5-1/2"	4842'	2898'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 4845' and found it open. Ran sand, sand bridged at 2175', knocked out bridge and checked top of sand to 4770' and dumped 5 sacks of cement. Pulled 55 jts of 5 1/2" casing to 1600' and pumped in 60 bbl of mud. Pulled rest of casing, cleared hole and mudded to 350', set rock bridge to 340' and ran 20 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor WestSupply Co., Inc.  
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.  
I, Noel J. Knight (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of August, 19 58

My commission expires 9-27-58 Thomas V. Dwyer Notary Public.

PLUGGING  
FILE SEC. 31 T. 30 R. 15W  
BOOK PAGE 112 LINE 21

AUG 19 1958 8-19-58  
CONSERVATION DIVISION

DRILLERS' LOG

Walker "B" No. 1  
Loc: C NW SW  
Sec: 31-30S-15W  
Barber County, Kansas  
Company: Honaker-Davis Drlg. Co., et al  
Contractor: Honaker-Davis Drlg. Co.

Comm: 5- 5-58  
Comp: 5-23-58  
Rotary Total Depth: 4990'  
Casing: 8 5/8" at 406'  
5 1/2" at 4842'

0	130	Gyp, Sand & Shale	
130	280	Shale, Shells & Gyp	
280	406	Shale & Shells	8 5/8" casing cemented at
406	620	Red Bed, Shale & Shells	406' with 300 sacks common
620	1085	Shale & Red Bed	cement and 2% calcium
1085	1280	Shale & Shells	chloride.
1280	1325	Shale & Gyp	
1325	1555	Shale & Shells	
1555	1700	Shale & Lime Shells	
1700	1900	Shale & Lime	
1900	2040	Shale & Shells	
2040	2095	Shale & Lime	
2095	2841	Lime & Shale	
2841	3670	Shale & Lime	
3670	3880	Lime	
3880	4085	Lime & Shale	
4085	4990	Lime	5 1/2" casing cemented at
4990		Rotary Total Depth	4842' with 125 sacks common
			cement with 2% Jel.

I certify that this the true and correct copy of the above log to the best of my knowledge.

H. S. Forbes  
H. S. Forbes

Subscribed and sworn to before me this 27th day of May, 1958.

Josephine Kopke  
Notary Public

My commission expires: Dec. 10, 1958

PLUGGING  
FILE SEC 31 T 30 R 15W  
BOOK PAGE 112 LINE 21

RECORDED  
MAY 31 1958  
COUNTY CLERK  
BARBER COUNTY, KANSAS