

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-20,733-00-00

LEASE NAME LAWRENZ

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

C NW 1/4-NE 1/4-NE 1/4
 SEC. 11 TWP. 30S RGE. 13 ~~XXXX~~ (W)

LEASE OPERATOR GOULD OIL INC.

ADDRESS 110 NORTH MARKET WICHITA, KS. 67202

COUNTY BARBER

PHONE#(316) 265-5523 OPERATORS LICENSE NO. 5298

Date Well Completed

Character of Well GAS

Plugging Commenced 12-9-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-11-91

The plugging proposal was approved on DEC. 10, 1991 (date)

by RICHARD LACEY (KCC District Agent's Name).

Is ACO-1 filled? YES If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 4730

Show depth and thickness of all water, oil and gas formations.

PBTD: 2831

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

Formation	Content	From	To	Size	Put In	Pulled out
		0	326	8 5/8	326	0 DEC 23 1991
		0	2875	4 1/2	2875	1968 FT. 62 JTS.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

TOP OF SAND: 2590. DUMPED 4SX CEMENT ON TOP OF SAND. SHOT OFF CASING AT 1968, PULLED 62 JTS.

TOP HOLE PLUG: 3 SX. HULLS, 10 SX. GEL, 50 SX. CEMENT, 10 SX. GEL, 100 # HULLS,

5/8 PLUG, 100 SX. CEMENT, 60-40 POZ. G & GEL. MAX. PRESSURE 500#, ISIP 200 #.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P.O. BOX 847 PRATT, KS. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GOULD OIL, INC.

STATE OF KANSAS COUNTY OF PRATT, ss.

JUDY BERRY

PLUGGING CONTRACTOR


(Employee of ~~Operator~~)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) P.W.S. Inc.

SUBSCRIBED AND SWORN TO before me this 20th day of Dec., 1991



Dorothy M. Furgason
 Notary Public

Commission Expires: Feb. 6, 1993