

ATE OF KANSAS
ATE CORPORATION COMMISSION
0 S. Market, Room 2078
chite, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-00722202-00-00

LEASE NAME Adams

WELL NUMBER #3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 33 TWP. 31 RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 9-8-98

Plugging Completed 9-10-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

EASE OPERATOR A.L. Abercrombie, Inc.

DRESS Rt. 1 Box 56 Great Bend, Ks. 67530

PHONE#(316) 793-8186 OPERATORS LICENSE NO. 5393

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 429' | None. |
| | | | | 4-1/2" | 3749' | 2400' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from feet to feet each side. Plugged off bottom with sand to 3669' and 4 sacks cement. Shot pipe @2600' and 2400'.

Pulled up to 600', pumped 10 sks. gel and 50 sks. cement, pulled to 400', pumped 40 sks. cement, pulled to 40' and circulated 25 sks. cement to surface. 60/40 pos, 6% gel.

Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

9-18-98

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: A.L. Abercrombie, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 17th day of September, 1998

[Signature]
Notary Public

My Commission Expires:

IRENE HERZBERG
State of Kansas
My Appt. Exp. Aug. 24, 2001

Form CP
Revised 05-

RECEIVED
KANSAS CORP. CO. 11:5